ES26-081 Lon Eilian, Caernarfon - Beech Developments - EXTRA INFO TAKE-OFF: BASIS & ASSUMPTIONS

4 x 2B1P flats = one pair of semis: Plot A/B and Plot C/D (each = GF flat + FF flat). C/D is the mirror of A/B -> identical quantities.

Waste / allowance rates (edit here - all sheets reference these cells)

Render (Dryvit) area	10%
Brick slips (flat)	10%
Corner slips	5%
Plasterboard	10%
Skirting / architrave / window board	10%
Beads / tape	10%

SOURCES	
Drawing	P1361-LEC-SAL-02-ZZ-DR-A-0007 P2 2B1P Flat Plans & Elevations (vector, 1:100 @ A2; 1 pt = 35.28 mm). Site elevations 0005 P04 (raster) for the porch lean-to.
Model data	04_Logs/specs/LE_spec.json (36 structural openings, wall set-out) and LE_partitions.json (timber partitions + internal doors). No SketchUp used.
Scripts	05_Scripts/le_xi_elev.py (elevation fills -> shapely), le_xi_takeoff.py (all measures -> JSON), le_xi_workbook.py (this workbook).
EXTERNAL FINISHES	
Measure	Render = cream fill (0.93,0.90,0.87); brick slips = brick fill (0.82,0.74,0.67) horizontal-lined zones; openings = frame/glass fills -> areas are NET of openings as drawn. FRONT / REAR / SIDE elevations are one plot (A/B); C/D mirrors.
Front elevation	Projection of the main front AND the stair-lobby front (one plot). Wall hidden behind the lean-to roof is roofed/internal - no finish.
Porch / stair lobby side wall	Not on the 0007 elevations: brick slips per the site side elevation. Trapezoid 1,741 long, 2360 at the lobby front rising at 23 deg to the main wall, less the lobby side window (710 x 1,300). One per plot.
Render system	Dryvit direct-applied finish over ICF EPS (Dryvit Outsulation-family base): rasp/level EPS, Dryvit Genesis (or Primus) base coat + Dryvit Standard Mesh, Dryvit primer, Dryvit textured finish (e.g. Sandpebble / Quarzputz). Thin-coat ~10 mm. Confirm build-up with Dryvit/Tremco technical (ICF substrate).
Brick slip system	Monolith brick slip system (adhesive-fixed slips on reinforced base coat over the ICF EPS, or rail/board fixed) - corner (L-shaped) slips at external corners and at reveals in slip zones. Product/fixing to be confirmed with Monolith.
Beads (render)	From the render polygon boundaries: base/starter at the bottom (incl. over the slip plinth), stop beads at render/slip junctions, under eaves/verge and at other edges; corner bead where render meets render on a building corner; reveal bead = jambs + head of every opening in render. Cills = window width (external cill by window supplier).
Reveals (external)	Frame set 1/3 back from the outer ICF face (118.5 mm): external reveal = 119 + finish (render 10 / slips 25).
INTERNAL LININGS	
Room geometry	Room polygons on the DRAWN finished faces (drawn walls: ext 421, party face 9,421, stair walls 386, partitions 119). Room areas checked against the drawn schedule (Floor Areas sheet).
Heights	GF walls FFL 0 -> u/s FF joists 2,575 (board height 2575). FF walls FFL 2,850 -> ceiling under the truss bottom chords on the plate (top 5,300) = 2450. Floor zone 2,575-2,850 excluded (except the stair-well band, measured separately).
Ceilings	GF ceiling = u/s FF floor = SEPARATING FLOOR between the GF and FF flats (fire 60 min + acoustic, ADB/ADE): 2 x 15 mm fire/acoustic board on resilient bars with mineral wool in the joist zone. Under-stair store soffit 2 x 15 mm fire. FF ceilings 12.5 mm + VCL under trusses (~5,300). Stair lobby ceiling under the lean-to on slope.
Board types	ICF faces: 12.5 mm wallboard screw-fixed to the ICF web strips / dabs + mechanical fixings (MR in bathrooms). Party wall + stair enclosure (6in Std ICF): 15 mm Type F fire board. Partitions: 15 mm each side on 38x89 studs (per LE_partitions build-up, drawn 119); MR in bathrooms. Boxing 12.5 MR.
Openings deducted	External openings: W x H inside the board zone (from LE_spec). Internal doors: gap x 2100 on both faces.
Internal reveals	Reveal depth = ICF 355.6 - 1/3 set-back 118.5 - frame 70 + lining 27.5 = 195 mm; jambs + head of every external opening.

Scrim / beads / skim	Board joints: walls net/1.2 m (vertical 1200 boards), ceilings net x (1/1.2 + 1/2.4). Internal angles = room internal corners x height + every room perimeter at the ceiling. Corner bead = room external corners x height + jambs/head of every external opening. Skim = all net wall + reveal + ceiling areas (face layer).
DOORS / JOINERY	
Leaves	From plan door gaps (LE_partitions): 910 -> 826 x 2040; 810 -> 726; 610 -> 526; 1,210 -> pair (cupboard). Linings 32 x (wall + 13).
Fire rule	FF floor 2.85 m < 4.5 m above ground: no protected entrance hall required in either flat (ADB Vol 1) - internal doors non-rated. Under-stair store door (W_c) opens from the GF flat into a store beneath the FF flat stair: FD30S self-closing as a precaution (confirm with Building Control). Flat entrance doors open to OUTSIDE: PAS 24 / SBD external doorsets (in structural schedule), not FD30S.
Ironmongery	1.5 pr hinges per leaf; tubular latch + lever pair; bathrooms: privacy lock + emergency release; cupboards: catch + pull (pair + flush bolt); FD30S: rated hinges, closer, intumescent + smoke seals, signage.
Skirting	Room floor perimeter on walls less every door width opening into that room (stair-well balustrade edge excluded).
Architrave	Per face = 2 legs x 2150 + (door gap + 2 x 70). Internal doors both faces; external doors one (inside) face.
Window boards	Length = structural width + 2 x 50 horns; depth = internal reveal 195 + 25 nosing = 220 mm (order 225 MDF/uPVC).
Not included	Concrete (measured from the model elsewhere), external doors/windows supply, roof/soffit/fascia, floor finishes, decorations, stair/balustrade.

1. External finishes - Monolith brick slips + Dryvit render over ICF (net of openings)

Item	Plot A/B (m2)	Plot C/D (m2)	TOTAL (m2)	Waste	TOTAL incl. waste	Notes
RENDER - Front (main + stair-lobby front)	16.30	16.30	32.60	3.26	35.86	elevation vector fill
RENDER - Rear	33.21	33.21	66.42	6.64	73.06	elevation vector fill
RENDER - Gable (side)	24.67	24.67	49.34	4.93	54.27	elevation vector fill
RENDER - Stair-lobby side wall (porch, site side elev.)	0.00	0.00	0.00	0.00	0.00	elevation vector fill
RENDER TOTAL (m2)	**74.18**	**74.18**	**148.36**	**14.84**	**163.20**	

Item	Plot A/B (m2)	Plot C/D (m2)	TOTAL (m2)	Waste	TOTAL incl. waste	Notes
BRICK SLIPS - Front (main + stair-lobby front)	18.22	18.22	36.44	3.64	40.08	elevation vector fill
BRICK SLIPS - Rear	6.95	6.95	13.90	1.39	15.29	elevation vector fill
BRICK SLIPS - Gable (side)	18.47	18.47	36.94	3.69	40.63	elevation vector fill
BRICK SLIPS - Stair-lobby side wall (porch, site side elev.)	3.83	3.83	7.66	0.77	8.43	trapezoid, see Basis
BRICK SLIP TOTAL (m2)	**47.47**	**47.47**	**94.94**	**9.49**	**104.43**	

Item	Plot A/B (m2)	Plot C/D (m2)	TOTAL (m2)	Waste	TOTAL incl. waste	Notes
Reveal returns in RENDER (jambs + heads x 129 mm) m2	5.12	5.12	10.24	1.02	11.26	add to render
Reveal returns in BRICK SLIP (jambs + heads x 144 mm) m2	3.29	3.29	6.58	0.66	7.24	slip returns / corner slips

Item	Plot A/B (m)	Plot C/D (m)	TOTAL (m)	Waste	TOTAL incl. waste	Notes
Render base / starter track (m)	15.72	15.72	31.44	3.14	34.58	
Render stop bead at render / slip junction (m)	37.75	37.75	75.50	7.55	83.05	
Render stop bead under eaves / verge / lean-to (m)	29.14	29.14	58.28	5.83	64.11	
Render stop bead, other edges (m)	14.62	14.62	29.24	2.92	32.16	
Render external corner bead (m)	5.10	5.10	10.20	1.02	11.22	
Render reveal bead: jambs + heads in render (m)	39.87	39.87	79.74	7.97	87.71	
Brick-slip corner slips: building corners (m)	7.57	7.57	15.14	0.76	15.90	
Brick-slip corner slips: reveals jambs + heads in slip zones (m)	22.89	22.89	45.78	2.29	48.07	
Brick-slip base support / starter (m)	40.11	40.11	80.22	8.02	88.24	
Window cills (external, by window width) (m)	14.24	14.24	28.48	2.85	31.33	

Corner (per plot)	Brick face 1 (m)	Brick face 2 (m)	Corner slips (m)	Render face 1 (m)	Render face 2 (m)	Render corner bead (m)
Front / gable corner	5.15	5.3	5.15	0	0	0
Rear / gable corner	0.06	0.15	0.06	5.1	5.26	5.1
Stair-lobby front / side corner	3.41	2.36	2.36	0.85	0	0

Elevation edge classification (per plot, m) - audit trail

FRONT: brick slip | external corner	5.25
FRONT: brick slip | junction (counted under render)	10.26

FRONT: brick slip | party line (continuous into C/D - none)	2.36
FRONT: brick slip | reveal (see opening sheet)	18.05
FRONT: brick slip | slip base support / starter	10.56
FRONT: brick slip | stop bead (other edge / internal angle)	11.1
FRONT: brick slip | top stop (eaves / verge / lean-to abutment)	5.24
FRONT: render | base / starter track	3.16
FRONT: render | party line (continuous into C/D - none)	1.9
FRONT: render | render / slip junction stop bead	12.89
FRONT: render | reveal (see opening sheet)	14.65
FRONT: render | stop bead (other edge / internal angle)	4.42
FRONT: render | top stop (eaves / verge / lean-to abutment)	14.68
REAR: brick slip | external corner	0.15
REAR: brick slip | junction (counted under render)	8.21
REAR: brick slip | party line (continuous into C/D - none)	0.15
REAR: brick slip | reveal (see opening sheet)	5.92
REAR: brick slip | slip base support / starter	16.97
REAR: brick slip | stop bead (other edge / internal angle)	0.3
REAR: render | base / starter track	8.53
REAR: render | external corner	5.1
REAR: render | party line (continuous into C/D - none)	5.1
REAR: render | render / slip junction stop bead	17.66
REAR: render | reveal (see opening sheet)	15.47
REAR: render | stop bead (other edge / internal angle)	10.2
REAR: render | top stop (eaves / verge / lean-to abutment)	9.54
SIDE: brick slip | external corner	5.49
SIDE: brick slip | junction (counted under render)	7.2
SIDE: brick slip | reveal (see opening sheet)	0.04
SIDE: brick slip | slip base support / starter	10.84
SIDE: brick slip | top stop (eaves / verge / lean-to abutment)	3.43
SIDE: render | base / starter track	4.03
SIDE: render | external corner	5.24
SIDE: render | render / slip junction stop bead	7.2
SIDE: render | reveal (see opening sheet)	8.2
SIDE: render | top stop (eaves / verge / lean-to abutment)	4.92

1b. External openings - finish at jambs/head, reveal lengths (external + internal)

Ref	Plot	Level	Elevation	Type	W mm	H mm	Jamb L finish	Jamb R finish	Head finish	Reveal in render m	Reveal in slips m	Ext cill m	Int reveal m (2H+W)
A/B-L1-F01	A/B	GF	Front	window	1570	1000	brick slip	brick slip	brick slip	0	3.57	1.57	3.57
A/B-L1-F02	A/B	GF	Front	window	740	1000	render	render	render	2.74	0	0.74	2.74
A/B-L1-F03	A/B	GF	Front	door	1040	2100	render	render	render	5.24	0	0	5.24
A/B-L1-LF04	A/B	GF	Stair-lobby front	door	1040	2100	brick slip	brick slip	brick slip	0	5.24	0	5.24
A/B-L1-LS05	A/B	GF	Stair-lobby side	window	710	1300	brick slip	brick slip	brick slip	0	3.31	0.71	3.31
A/B-L1-R07	A/B	GF	Rear	door	1040	2100	render	render	render	5.24	0	0	5.24
A/B-L1-R08	A/B	GF	Rear	window	1010	1300	brick slip	render	render	2.31	1.3	1.01	3.61
A/B-L1-R09	A/B	GF	Rear	window	1580	1300	render	brick slip	render	2.88	1.3	1.58	4.18
A/B-L1-G10	A/B	GF	Gable	window	730	1300	render	render	render	3.33	0	0.73	3.33
A/B-L2-F11	A/B	FF	Front	window	1570	1000	brick slip	brick slip	brick slip	0	3.57	1.57	3.57
A/B-L2-F12	A/B	FF	Front	window	740	1000	render	render	render	2.74	0	0.74	2.74
A/B-L2-F13	A/B	FF	Front	window	760	1000	render	brick slip	render	1.76	1	0.76	2.76
A/B-L2-F14	A/B	FF	Front	window	770	1000	brick slip	render	render	1.77	1	0.77	2.77
A/B-L2-R15	A/B	FF	Rear	window	750	1300	render	render	render	3.35	0	0.75	3.35
A/B-L2-R16	A/B	FF	Rear	window	1010	1300	brick slip	render	render	2.31	1.3	1.01	3.61
A/B-L2-R17	A/B	FF	Rear	window	1580	1300	render	brick slip	render	2.88	1.3	1.58	4.18
A/B-L2-G18	A/B	FF	Gable	window	720	1300	render	render	render	3.32	0	0.72	3.32
C/D-L1-F01	C/D	GF	Front	window	1570	1000	brick slip	brick slip	brick slip	0	3.57	1.57	3.57
C/D-L1-F02	C/D	GF	Front	window	740	1000	render	render	render	2.74	0	0.74	2.74
C/D-L1-F03	C/D	GF	Front	door	1040	2100	render	render	render	5.24	0	0	5.24
C/D-L1-LF04	C/D	GF	Stair-lobby front	door	1040	2100	brick slip	brick slip	brick slip	0	5.24	0	5.24
C/D-L1-LS05	C/D	GF	Stair-lobby side	window	710	1300	brick slip	brick slip	brick slip	0	3.31	0.71	3.31
C/D-L1-R07	C/D	GF	Rear	door	1040	2100	render	render	render	5.24	0	0	5.24
C/D-L1-R08	C/D	GF	Rear	window	1010	1300	brick slip	render	render	2.31	1.3	1.01	3.61
C/D-L1-R09	C/D	GF	Rear	window	1580	1300	render	brick slip	render	2.88	1.3	1.58	4.18
C/D-L1-G10	C/D	GF	Gable	window	730	1300	render	render	render	3.33	0	0.73	3.33
C/D-L2-F11	C/D	FF	Front	window	1570	1000	brick slip	brick slip	brick slip	0	3.57	1.57	3.57
C/D-L2-F12	C/D	FF	Front	window	740	1000	render	render	render	2.74	0	0.74	2.74
C/D-L2-F13	C/D	FF	Front	window	760	1000	render	brick slip	render	1.76	1	0.76	2.76

C/D-L2-F14	C/D	FF	Front	window	770	1000 brick slip	render	render	1.77	1	0.77	2.77
C/D-L2-R15	C/D	FF	Rear	window	750	1300 render	render	render	3.35	0	0.75	3.35
C/D-L2-R16	C/D	FF	Rear	window	1010	1300 brick slip	render	render	2.31	1.3	1.01	3.61
C/D-L2-R17	C/D	FF	Rear	window	1580	1300 render	brick slip	render	2.88	1.3	1.58	4.18
C/D-L2-G18	C/D	FF	Gable	window	720	1300 render	render	render	3.32	0	0.72	3.32
TOTAL (both plots)									**79.74**	**45.78**	**28.48**	**125.52**

2. Internal plasterboard by surface (m2, per plot = GF flat + FF flat)

Surface	Gross m2 (A/B)	Openings m2	Net A/B	Net C/D	NET TOTAL	Layers	Board m2 incl. Waste		Board to order	Board type	Measure
GF external walls - internal face (ICF)	61.52	14.10	47.42	47.42	94.84	1	94.84	9.48	104.32	12.5 mm wallboard, screw-fixed to ICF web strips / dabs + mech. fixings (MR board in	perimeter 23.89 m x 2.575 m; excludes floor zone 2,575-2,850
GF party wall - this flat side	18.62	0.00	18.62	18.62	37.24	1	37.24	3.72	40.96	15 mm fire-rated (Type F) board on dabs/battens	7.23 m x 2.575
GF stair-enclosure walls (6in Std) - both faces	31.88	3.78	28.10	28.10	56.20	1	56.20	5.62	61.82	15 mm fire-rated (Type F) board	12.38 m (all room faces) x 2.575; W_c door deducted both faces
GF timber partitions - both faces	87.73	19.95	67.78	67.78	135.56	1	135.56	13.56	149.12	15 mm board on 38x89 studs (per LE_partitions build-up); MR in bathroom	34.07 m of room faces x 2.575
GF riser boxing - room face	2.58	0.00	2.58	2.58	5.16	1	5.16	0.52	5.68	12.5 mm MR board on 38x47	1.00 m x 2.575
FF external walls - internal face (ICF)	54.41	9.12	45.29	45.29	90.58	1	90.58	9.06	99.64	12.5 mm wallboard, screw-fixed to ICF web strips / dabs + mech. fixings (MR board in	perimeter 22.21 m x 2.450 m; excludes floor zone 2,575-2,850
FF party wall - this flat side	13.74	0.00	13.74	13.74	27.48	1	27.48	2.75	30.23	15 mm fire-rated (Type F) board on dabs/battens	5.61 m x 2.450
FF stair-enclosure walls (6in Std) - both faces	23.72	0.00	23.72	23.72	47.44	1	47.44	4.74	52.18	15 mm fire-rated (Type F) board	9.68 m (all room faces) x 2.450; W_c door deducted both faces
FF timber partitions - both faces	85.73	22.51	63.22	63.22	126.44	1	126.44	12.64	139.08	15 mm board on 38x89 studs (per LE_partitions build-up); MR in bathroom	34.99 m of room faces x 2.450
FF riser boxing - room face	2.45	0.00	2.45	2.45	4.90	1	4.90	0.49	5.39	12.5 mm MR board on 38x47	1.00 m x 2.450
GF ceilings (u/s FF separating floor)	45.53	0.00	45.53	45.53	91.06	2	182.12	18.21	200.33	2 x 15 mm fire/acoustic board (e.g. SoundBloc/FireLine) on resilient bars - separating fl	GF flat rooms; stair foot is under the FF stair-well (in FF ceiling)
GF store ceiling = stair soffit	3.24	0.00	3.24	3.24	6.48	2	12.96	1.30	14.26	2 x 15 mm fire-rated (60 min soffit to FF flat stair over GF flat)	plan area
GF stair-lobby ceiling (u/s lean-to)	2.09	0.00	2.09	2.09	4.18	1	4.18	0.42	4.60	12.5 mm board under lean-to rafters	lobby 1,460 x 1,320 on slope 23 deg
FF ceilings (u/s trusses ~5,300)	49.81	0.00	49.81	49.81	99.62	1	99.62	9.96	109.58	12.5 mm board + VCL (15 mm Type F if BCO requires) under bottom chords	incl. stair-well void area
Stair-well floor-zone band (2,575-2,850)	1.27	0.00	1.27	1.27	2.54	1	2.54	0.25	2.79	15 mm fire-rated board	W_a + party + front faces of the void x 275
Internal reveals (jambs + heads, ext. openings)	12.21	0.00	12.21	12.21	24.42	1	24.42	2.44	26.86	12.5 mm board / bonding + skim	62.76 m x 195 mm
TOTAL	**496.53**	**69.46**	**427.07**	**427.07**	**854.14**		**951.68**	**95.17**	**1046.85**		

Item	Plot A/B (m / m2)	Plot C/D (m / m2)	TOTAL (m / m2)	Waste	TOTAL incl. waste	Notes
Plasterboard net, walls + reveals (m2)	326.39	326.39	652.78	65.28	718.06	
Plasterboard net, ceilings (m2)	100.67	100.67	201.34	20.13	221.47	
Scrim tape: board joints (m)	397.83	397.83	795.66	79.57	875.23	
Scrim tape: internal angles wall-wall (m)	183.60	183.60	367.20	36.72	403.92	
Scrim tape: wall-ceiling angles (m)	152.01	152.01	304.02	30.40	334.42	
Corner bead: external corners in rooms (m)	32.60	32.60	65.20	6.52	71.72	
Corner bead: window/door reveals (m)	62.76	62.76	125.52	12.55	138.07	
Skim coat (m2)	427.06	427.06	854.12	85.41	939.53	

Check: partition run lengths in LE_partitions.json (one face, A/B) GF 17.99 m / FF 18.02 m

2b. Room wall faces by type (A/B; m of face) - feeds sheet 2

Level	Room	Flat	EXT	PARTY	STAIR	PARTITION	BOXING	Wall h mm	Int corners	Ext corners	Ceiling m2
GF	Living/Kitchen	GF flat	10.84	0	0	9.28	0	2575	6	2	20.57
GF	Cupboard (G8/G9, unlabelled)	GF flat	1.7	0	0	1.7	0	2575	4	0	0.72
GF	Bathroom	GF flat	1.66	0	0	6.06	1	2575	5	1	4.51
GF	Hall	GF flat	1.39	0	1.77	8.17	0	2575	5	1	5.51
GF	Bedroom 1	GF flat	4.83	2.75	2.3	5.28	0	2575	4	0	13.27
GF	A/C / Laundry	GF flat	0.69	0	2.07	1.38	0	2575	4	0	0.95
GF	Store (under stair, via W_c)	GF flat	0	2.14	4.86	1.1	0	2575	5	1	3.24
GF	Stairs / entrance lobby (FF flat)	FF flat	2.78	2.34	1.38	1.1	0	2575	5	1	3.05
FF	Living/Kitchen	FF flat	10.84	0	0	9.28	0	2450	6	2	20.57
FF	Cupboard (F6/F7, unlabelled)	FF flat	1.7	0	0	1.7	0	2450	4	0	0.72
FF	Bathroom	FF flat	1.66	0	0	6.06	1	2450	5	1	4.51
FF	Hall + landing (incl. stair well)	FF flat	1.1	2.86	5.24	8.67	0	2450	8	4	8.83
FF	Bedroom 1	FF flat	4.83	2.75	2.3	5.28	0	2450	4	0	13.27
FF	A/C / Laundry	FF flat	1.32	0	0	2.62	0	2450	4	0	0.86
FF	Store	FF flat	0.76	0	2.14	1.38	0	2450	4	0	1.05

3. Doors - internal doorsets + ironmongery (per plot; C/D identical, handed)

Ref	Level	Wall	Between	Gap mm	Leaf	Leaves	Fire	Lining	Hinges pr	Ironmongery set	Qty A/B	Qty C/D	Qty TOTAL
ID01	GF	G1	Hall / Bedroom 1	910	826 x 2040 x 35	1	-	32 x 132 lining set (partition 119)	1.5	standard set: 1.5 pr hinges, tubular latch, lever pair	1	1	2
ID02	GF	G2	Living/Kitchen / Hall	910	826 x 2040 x 35	1	-	32 x 132 lining set (partition 119)	1.5	standard set: 1.5 pr hinges, tubular latch, lever pair	1	1	2
ID03	GF	G5	Bathroom / Hall	910	826 x 2040 x 35	1	-	32 x 132 lining set (partition 119)	1.5	bathroom set: 1.5 pr hinges, bathroom privacy lock + thumb-turn/release, lever pair	1	1	2
ID04	GF	G6	Hall / A/C / Laundry	1210	pair 2 x 533 x 1981 (or 2 x 526 x 2040)	2	-	32 x 132 lining set (partition 119)	3	cupboard set per leaf: 1.5 pr hinges, ball/roller catch, pull/lever; pair: + flush bolt	1	1	2
ID05	GF	G8	Cupboard (G8/G9, unlabelled) / Living/Kitchen	810	726 x 2040 x 35	1	-	32 x 132 lining set (partition 119)	1.5	cupboard set per leaf: 1.5 pr hinges, ball/roller catch, pull/lever; pair: + flush bolt	1	1	2
ID06	FF	F1	Hall + landing (incl. stair well) / Bedroom 1	910	826 x 2040 x 35	1	-	32 x 132 lining set (partition 119)	1.5	standard set: 1.5 pr hinges, tubular latch, lever pair	1	1	2
ID07	FF	F2	Living/Kitchen / Hall + landing (incl. stair well)	910	826 x 2040 x 35	1	-	32 x 132 lining set (partition 119)	1.5	standard set: 1.5 pr hinges, tubular latch, lever pair	1	1	2
ID08	FF	F3	Bathroom / Hall + landing (incl. stair well)	910	826 x 2040 x 35	1	-	32 x 132 lining set (partition 119)	1.5	bathroom set: 1.5 pr hinges, bathroom privacy lock + thumb-turn/release, lever pair	1	1	2
ID09	FF	F6	Cupboard (F6/F7, unlabelled) / Living/Kitchen	810	726 x 2040 x 35	1	-	32 x 132 lining set (partition 119)	1.5	cupboard set per leaf: 1.5 pr hinges, ball/roller catch, pull/lever; pair: + flush bolt	1	1	2
ID10	FF	F8	Hall + landing (incl. stair well) / Store	610	526 x 2040 x 35	1	-	32 x 132 lining set (partition 119)	1.5	cupboard set per leaf: 1.5 pr hinges, ball/roller catch, pull/lever; pair: + flush bolt	1	1	2
ID11	FF	F9	A/C / Laundry / Hall + landing (incl. stair well)	1210	pair 2 x 533 x 1981 (or 2 x 526 x 2040)	2	-	32 x 132 lining set (partition 119)	3	cupboard set per leaf: 1.5 pr hinges, ball/roller catch, pull/lever; pair: + flush bolt	1	1	2
ID12	GF	W_c (ICF 6in Std)	Hall / Store (under stair, via W_c)	900	826 x 2040 x 35	1	FD30S self-closing (confirm with	ICF reveal: 32 x 315 lining (6in Std 285.75 + board	1.5	FD30S set: 1.5 pr intumescent-rated hinges/leaf, fire-rated latch, lever pair, self-closer, intumesce	1	1	2

SUMMARY

Door sets / linings (no.)	12	12	24
Door leaves (no.)	14	14	28
Hinges (pairs)	21	21	42
Bathroom privacy lock sets	2	2	4
FD30S sets (closer + seals)	1	1	2
Standard latch sets	4	4	8
Cupboard catch sets (doorsets)	5	5	10

EXTERNAL DOORS (from the structural opening schedule; supply by others / window package)

Ref	Level	Elevation	Note	W mm	H mm	Qty A/B	Qty C/D	Qty TOTAL
AB-L1-FC	GF	Front	GF flat entrance door (XD02)	1040	2100	1	1	2
AB-L1-LF	GF	Stair-lobby front	FF flat entrance door, stair lobby (WG01)	1040	2100	1	1	2
AB-L1-RC	GF	Rear	GF rear door, living/kitchen	1040	2100	1	1	2

4. Skirtings and architraves - linear m by room and plot

Level	Room	Flat	Perimeter on walls m	Door widths m	Skirting A/B m	Skirting C/D m	Skirting TOTAL m	
GF	Living/Kitchen	GF flat	20.11	2.76	17.35	17.35	34.7	
GF	Cupboard (G8/G9, unlabelled)	GF flat	3.4	0.81	2.59	2.59	5.18	
GF	Bathroom	GF flat	8.72	0.91	7.81	7.81	15.62	
GF	Hall	GF flat	11.33	5.88	5.45	5.45	10.9	
GF	Bedroom 1	GF flat	15.15	0.91	14.24	14.24	28.48	
GF	A/C / Laundry	GF flat	4.13	1.21	2.92	2.92	5.84	
GF	Store (under stair, via W_c)	GF flat	8.1	0.9	7.2	7.2	14.4	
GF	Stairs / entrance lobby (FF flat)	FF flat	7.6	1.04	6.56	6.56	13.12	
FF	Living/Kitchen	FF flat	20.11	1.72	18.39	18.39	36.78	
FF	Cupboard (F6/F7, unlabelled)	FF flat	3.4	0.81	2.59	2.59	5.18	
FF	Bathroom	FF flat	8.72	0.91	7.81	7.81	15.62	
FF	Hall + landing (incl. stair well)	FF flat	13.25	4.55	8.7	8.7	17.4	
FF	Bedroom 1	FF flat	15.15	0.91	14.24	14.24	28.48	
FF	A/C / Laundry	FF flat	3.94	1.21	2.73	2.73	5.46	
FF	Store	FF flat	4.27	0.61	3.66	3.66	7.32	
	SKIRTING TOTAL				**122.24**	**122.24**	**244.48**	268.928 incl. waste

Ref	Door	Faces	m per face	Architrave A/B m	Architrave C/D m	Architrave TOTAL m
ID01	Hall / Bedroom 1 (910)	2	5.35	10.7	10.7	21.4
ID02	Living/Kitchen / Hall (910)	2	5.35	10.7	10.7	21.4
ID03	Bathroom / Hall (910)	2	5.35	10.7	10.7	21.4
ID04	Hall / A/C / Laundry (1210)	2	5.65	11.3	11.3	22.6
ID05	Cupboard (G8/G9, unlabelled) / Living/Kitche	2	5.25	10.5	10.5	21
ID06	Hall + landing (incl. stair well) / Bedroom 1 (9	2	5.35	10.7	10.7	21.4
ID07	Living/Kitchen / Hall + landing (incl. stair well	2	5.35	10.7	10.7	21.4
ID08	Bathroom / Hall + landing (incl. stair well) (91	2	5.35	10.7	10.7	21.4
ID09	Cupboard (F6/F7, unlabelled) / Living/Kitcher	2	5.25	10.5	10.5	21

ID10	Hall + landing (incl. stair well) / Store (610)	2	5.05	10.1	10.1	20.2	
ID11	A/C / Laundry / Hall + landing (incl. stair well	2	5.65	11.3	11.3	22.6	
ID12	Hall / Store (under stair, via W_c) (900)	2	5.34	10.68	10.68	21.36	
AB-L1-FGF flat entrance door (XD02) (1040)		1	5.48	5.48	5.48	10.96	
AB-L1-LFF flat entrance door, stair lobby (WG01) (10		1	5.48	5.48	5.48	10.96	
AB-L1-FGF rear door, living/kitchen (1040)		1	5.48	5.48	5.48	10.96	
	ARCHITRAVE TOTAL			**145.02**	**145.02**	**290.04**	319.044 incl. waste

5. Floor areas by room (drawn schedule vs geometry check)

Level	Room	Flat	Drawn area m2	Geometry m2	Diff m2	A/B m2 (drawn, else geom)	C/D m2	TOTAL m2	Note
GF	Living/Kitchen	GF flat	20.6	20.57	-0.03	20.6	20.6	41.2	
GF	Cupboard (G8/G9, unlabelled)	GF flat		0.72		0.72	0.72	1.44	not named on drawing - part of Living/Kitchen zone
GF	Bathroom	GF flat	4.5	4.51	0.01	4.5	4.5	9	
GF	Hall	GF flat	5.5	5.51	0.01	5.5	5.5	11	
GF	Bedroom 1	GF flat	13.3	13.27	-0.03	13.3	13.3	26.6	
GF	A/C / Laundry	GF flat	0.9	0.95	0.05	0.9	0.9	1.8	
GF	Store (under stair, via W_c)	GF flat	2.9	3.24	0.34	2.9	2.9	5.8	geometry = full plan area under the stair; drawn 2.9 likely headroom-limited
GF	Stairs / entrance lobby (FF flat)	FF flat	2.5	3.05	0.55	2.5	2.5	5	drawn 2.5 (GIFA table 2.4) - geometry incl. stair foot; FF flat area at GF
FF	Living/Kitchen	FF flat	20.6	20.57	-0.03	20.6	20.6	41.2	
FF	Cupboard (F6/F7, unlabelled)	FF flat		0.72		0.72	0.72	1.44	not named on drawing
FF	Bathroom	FF flat	4.5	4.51	0.01	4.5	4.5	9	
FF	Hall + landing (incl. stair well)	FF flat	10.5	6.88	-3.62	10.5	10.5	21	geometry excludes the stair-well void (1.94 m2); drawn 10.5 includes it + landing
FF	Bedroom 1	FF flat	13.3	13.27	-0.03	13.3	13.3	26.6	
FF	A/C / Laundry	FF flat	0.9	0.86	-0.04	0.9	0.9	1.8	
FF	Store	FF flat	1.1	1.05	-0.05	1.1	1.1	2.2	
	GF TOTAL (rooms)					50.92	50.92	101.84	
	FF TOTAL (rooms)					51.62	51.62	103.24	
	Drawing GIFA: GF flat 53.0 m2; FF flat 54.0 m2 + 2.4 m2 at GF = 56.4 m2 (per flat)								

6. Structural opening schedule (LE_spec.json, both plots)

Ref	Plot	Level	Elevation	Type	W mm	H mm	Sill mm (FFL 0)	Head mm	Wall type	Note
AB-L1-F01	A/B	GF	Front	window	1570	1000	1100	2100	6in XR35 (355.6)	GF kitchen (WG02)
AB-L1-F02	A/B	GF	Front	window	740	1000	1100	2100	6in XR35 (355.6)	GF bathroom
AB-L1-F03	A/B	GF	Front	door	1040	2100	0	2100	6in XR35 (355.6)	GF flat entrance door (XD02)
AB-L1-LF04	A/B	GF	Stair-lobby front	door	1040	2100	0	2100	6in XR35 (355.6)	FF flat entrance door, stair lobby (WG01)
AB-L1-LS05	A/B	GF	Stair-lobby side	window	710	1300	800	2100	6in XR35 (355.6)	stair lobby side window (site side elevation: as WG03)
AB-L1-WC06	A/B	GF	Internal stair wall W_c	door	900	2100	0	2100	6in Std (285.75) - stair enclosure	GF under-stair store door (6in Std stair wall)
AB-L1-R07	A/B	GF	Rear	door	1040	2100	0	2100	6in XR35 (355.6)	GF rear door, living/kitchen
AB-L1-R08	A/B	GF	Rear	window	1010	1300	800	2100	6in XR35 (355.6)	GF rear window, hall/bedroom
AB-L1-R09	A/B	GF	Rear	window	1580	1300	800	2100	6in XR35 (355.6)	GF bedroom window
AB-L1-G10	A/B	GF	Gable	window	730	1300	800	2100	6in XR35 (355.6)	GF gable window, living (WG03)
AB-L2-F11	A/B	FF	Front	window	1570	1000	3950	4950	6in XR35 (355.6)	FF kitchen
AB-L2-F12	A/B	FF	Front	window	740	1000	3950	4950	6in XR35 (355.6)	FF bathroom
AB-L2-F13	A/B	FF	Front	window	760	1000	3950	4950	6in XR35 (355.6)	FF A/C laundry
AB-L2-F14	A/B	FF	Front	window	770	1000	3950	4950	6in XR35 (355.6)	FF stair
AB-L2-R15	A/B	FF	Rear	window	750	1300	3650	4950	6in XR35 (355.6)	FF rear living
AB-L2-R16	A/B	FF	Rear	window	1010	1300	3650	4950	6in XR35 (355.6)	FF rear hall/bedroom
AB-L2-R17	A/B	FF	Rear	window	1580	1300	3650	4950	6in XR35 (355.6)	FF bedroom
AB-L2-G18	A/B	FF	Gable	window	720	1300	3650	4950	6in XR35 (355.6)	FF gable window, living
CD-L1-F01	C/D	GF	Front	window	1570	1000	1100	2100	6in XR35 (355.6)	GF kitchen (WG02)
CD-L1-F02	C/D	GF	Front	window	740	1000	1100	2100	6in XR35 (355.6)	GF bathroom
CD-L1-F03	C/D	GF	Front	door	1040	2100	0	2100	6in XR35 (355.6)	GF flat entrance door (XD02)
CD-L1-LF04	C/D	GF	Stair-lobby front	door	1040	2100	0	2100	6in XR35 (355.6)	FF flat entrance door, stair lobby (WG01)
CD-L1-LS05	C/D	GF	Stair-lobby side	window	710	1300	800	2100	6in XR35 (355.6)	stair lobby side window (site side elevation: as WG03)
CD-L1-WC06	C/D	GF	Internal stair wall W_c	door	900	2100	0	2100	6in Std (285.75) - stair enclosure	GF under-stair store door (6in Std stair wall)
CD-L1-R07	C/D	GF	Rear	door	1040	2100	0	2100	6in XR35 (355.6)	GF rear door, living/kitchen
CD-L1-R08	C/D	GF	Rear	window	1010	1300	800	2100	6in XR35 (355.6)	GF rear window, hall/bedroom
CD-L1-R09	C/D	GF	Rear	window	1580	1300	800	2100	6in XR35 (355.6)	GF bedroom window
CD-L1-G10	C/D	GF	Gable	window	730	1300	800	2100	6in XR35 (355.6)	GF gable window, living (WG03)
CD-L2-F11	C/D	FF	Front	window	1570	1000	3950	4950	6in XR35 (355.6)	FF kitchen
CD-L2-F12	C/D	FF	Front	window	740	1000	3950	4950	6in XR35 (355.6)	FF bathroom
CD-L2-F13	C/D	FF	Front	window	760	1000	3950	4950	6in XR35 (355.6)	FF A/C laundry
CD-L2-F14	C/D	FF	Front	window	770	1000	3950	4950	6in XR35 (355.6)	FF stair
CD-L2-R15	C/D	FF	Rear	window	750	1300	3650	4950	6in XR35 (355.6)	FF rear living
CD-L2-R16	C/D	FF	Rear	window	1010	1300	3650	4950	6in XR35 (355.6)	FF rear hall/bedroom
CD-L2-R17	C/D	FF	Rear	window	1580	1300	3650	4950	6in XR35 (355.6)	FF bedroom

CD-L2-G18	C/D	FF	Gable	window	720	1300	3650	4950 6in XR35 (355.6)	FF gable window, living

Windows	28
Doors	8

7. Window boards - length = W + 2 x 50 horns, depth 220 mm

Ref	Plot	Level	Elevation	Opening W mm	Board length mm	Board depth mm	Length m
A/B-L1-F01	A/B	GF	Front	1570	1670	220	1.67
A/B-L1-F02	A/B	GF	Front	740	840	220	0.84
A/B-L1-LS05	A/B	GF	Stair-lobby side	710	810	220	0.81
A/B-L1-R08	A/B	GF	Rear	1010	1110	220	1.11
A/B-L1-R09	A/B	GF	Rear	1580	1680	220	1.68
A/B-L1-G10	A/B	GF	Gable	730	830	220	0.83
A/B-L2-F11	A/B	FF	Front	1570	1670	220	1.67
A/B-L2-F12	A/B	FF	Front	740	840	220	0.84
A/B-L2-F13	A/B	FF	Front	760	860	220	0.86
A/B-L2-F14	A/B	FF	Front	770	870	220	0.87
A/B-L2-R15	A/B	FF	Rear	750	850	220	0.85
A/B-L2-R16	A/B	FF	Rear	1010	1110	220	1.11
A/B-L2-R17	A/B	FF	Rear	1580	1680	220	1.68
A/B-L2-G18	A/B	FF	Gable	720	820	220	0.82
C/D-L1-F01	C/D	GF	Front	1570	1670	220	1.67
C/D-L1-F02	C/D	GF	Front	740	840	220	0.84
C/D-L1-LS05	C/D	GF	Stair-lobby side	710	810	220	0.81
C/D-L1-R08	C/D	GF	Rear	1010	1110	220	1.11
C/D-L1-R09	C/D	GF	Rear	1580	1680	220	1.68
C/D-L1-G10	C/D	GF	Gable	730	830	220	0.83
C/D-L2-F11	C/D	FF	Front	1570	1670	220	1.67
C/D-L2-F12	C/D	FF	Front	740	840	220	0.84
C/D-L2-F13	C/D	FF	Front	760	860	220	0.86
C/D-L2-F14	C/D	FF	Front	770	870	220	0.87
C/D-L2-R15	C/D	FF	Rear	750	850	220	0.85
C/D-L2-R16	C/D	FF	Rear	1010	1110	220	1.11

C/D-L2-R17	C/D	FF	Rear	1580	1680	220	1.68	
C/D-L2-G18	C/D	FF	Gable	720	820	220	0.82	
Plot A/B	14						15.64	
Plot C/D	14						15.64	
TOTAL	28						31.28	34.408 incl. waste